




# MINISTRY OF INFRASTRUCTURE, COMMUNICATION UTILITIES, HOUSING & TOURISM

PROCUREMENT #2021/MICUHT/AP/BPFT/1-1.0



## RESPONSES TO QUERY #1

DRAWING No. E-2 ELECTRICAL DETAILS

### A. MAIN ELECTRICAL SCHEMATIC

- 1) Main Disconnect Switch on Schematic Shows 600 Amp 3 Pole Main, however in your Price Bill you are requesting an 800 Amp 3 Pole Main Disconnect. Please verified.  
**The Main Disconnect will be 800 Amps 3pole. An addendum will be issued to correct this information.**
- 2) Location of Main Distribution Board not shown on Ground Floor Power.  
**This is shown in the Generator Building Drawing.**
- 3) Location of Main Disconnect Not Shown on Ground Floor Power.  
**This is shown in the Generator Building Drawing.**
- 4) Location of Stand by Generator not shown on either Ground Floor Power of External Drawings.  
**This is shown in the Generator Building Drawing.**
- 5) Location of Automatic Transfer Switch (ATS) not Shown on Ground Floor Power.  
**This is shown in the Generator Building Drawing.**
- 6) Panel Board – V1 - West Vendor Ground Floor - Location of Panel Board NOT Shown  
**This is shown on Drawing E-4 & E-5.**
- 7) Panel Board – V2 – East Vendor Ground Floor – Location of Panel Board NOT Shown.  
**This is shown on Drawing E-4 & E-5.**
- 8) Panel Board – V3 – Departure Seating Vendor Ground Floor – Location of Panel Board NOT Shown.  
**This is to be located in the Departure seating vendor room. An addendum will be issued to show this information.**
- 9) PANEL BOARD – FFP – Main Breaker on Schematic Shows 400 Amp 3 Pole Main Breaker, Supply from Main Distribution Panel Board shown 200 Amp 3 Pole.  
**This will be a 200A 3pole Panel. An addendum will be issued to correct this information.**

10) Panel Board Air Condition AC – Not Shown

**This is shown on Drawing E-7.**

11) West External Panel Board Ground Floor – NOT Shown

**This is shown in the Generator Building Drawing**

12) Generator House Pane Board – NOT Shown

**This is shown in the Generator Building Drawing.**

**B. PRICE BILL OF QUANTITIES**

1) Pages 1 and 2 are repeated on Pages 3 and 4, however the quantities are different. Please indicate which Price Bills are through and correct.

**Electrical Installation and supply of materials are separated in the BOQ. Supply quantities are intentionally 5 – 10% more to facilitate for material delivered damaged and to create a maintenance stock at the end of the project.**

**Attachments: None**



---

Chairman Procurement Committee

---

**END OF RESPONSE TO QUERRY #1**